

Project Profile



A challenging area that's always in question. The solution was to fill the uneven gaps with spray urethane foam, carve away excess foam, and then cover with Base Coat and Fabric.

Commercial Metal Roof

Project Specifications

- Department of Transportation, South Carolina
- Metal Roof
- ♦ Approx. 15,000 SQ FT

About the project:

This metal roof was slated to be torn off but the Acrylabs System enabled the SC DOT to save a costly expense. The savings led to adding more roof projects to the list. The standard Acrylabs PR-20 system for metal roofs includes addressing all seams, details, and fasteners to create a seamless membrane. Skylights were restored with Acrylabs NewClear and outlined with Acrylabs Safety Yellow.



Fiberglass skylights are hard to see and create a dangerous hazard on roofs



Contractor applying Safety Yellow around perimeter of Sky light making it more visible and safe

