

Project Profile



Installing 12" fabric around perimeter and details

Residential Deck Project

Project Specifications

- Clifton, NJ
- Existing fiberglass with peeling paint
- ♦ Approx. 15'x20'

About the project:

This project was completed by a New York contractor on a residential deck project in Clifton, New Jersey. It had a failing fiberglass system with peeling paint. The contractor scraped off the peeling paint, power washed clean, then applied Acrylabs Base System and DEK-coat finishes.



Installing Acrylabs Base System



Using Brushable Sealant to smooth out the blemishes

DEK-coat finishes applied

